DRAWING NUMBER: MD-216-1000-EG-CV-DED-1001 | REV: D01

1.0 GENERAL:

1.1 ALL DIMENSIONS ARE GIVEN IN MILLIMETRES UNLESS NOTED OTHERWISE.
1.2 ALL LEVELS ARE GIVEN IN METRES UNLESS NOTED OTHERWISE.
1.3 ALL WORKS SHALL BE UNDERTAKEN IN ACCORDANCE WITH THE LATEST EMPLOYER APPROVED, SIGNED AND STAMPED EDITIONS OF RELEVANT STANDARDS AND THEIR AMENDMENTS, PROJECT SPECIFICATIONS AND THE DESIGN AND STANDARD DRAWINGS AS SPECIFIED.
1.4 DESIGN DRAWINGS SHALL NOT BE SCALED AND ALL DIMENSIONS SHALL BE READ DIRECTLY FROM DESIGN DRAWINGS. ANY DISCREPANCIES WITHIN THE DOCUMENTATION SHALL BE REFERRED TO THE EPC FOR CLARIFICATION BEFORE PROCEEDING.
1.5 PRODUCTS EQUIVALENT TO THOSE SPECIFIED ON THE DESIGN DRAWINGS MAY BE USED ONLY WITH APPROVAL OF THE EPC.
1.6 FOR PROJECT SPECIFIC NOTES REFER TO DESIGN DRAWINGS.
1.7 VERTICAL DATUM (TO BE SPECIFIED).
1.8 HORIZONTAL GRID (TO BE SPECIFIED).

2.0 EXCAVATION AND FOUNDATIONS :

2.1 EXCAVATION AND FOUNDATION PREPARATION SHALL COMPLY WITH STANDARD SPECIFICATION MD-101-SMEM-EG-CV-SPC-0001.
2.2 NO BACKFILLING SHALL COMMENCE AGAINST WALLS UNTIL 28 DAYS HAVE ELAPSED FROM COMPLETION OF THE CONCRETE POUR OR APPROVED PROPPING HAS BEEN INSTALLED.
2.3 ANY OVER EXCAVATION AT FOOTING LOCATIONS SHALL BE MADE GOOD WITH STRUCTURAL FILL COMPACTED TO AT LEAST THE BEARING CAPACITY OF THE SURROUNDING UNDISTURBED SOIL IN ACCORDANCE WITH STANDARD SPECIFICATION MD-101-SMEM-EG-CV-SPC-0001. ALTERNATIVELY LEAN MIX CONCRETE MAY BE USED.
2.4 SOIL UNDER SLABS ON GRADE SHALL BE COMPACTED TO A MINIMUM DEPTH OF 300 mm TO ACHIEVE 95% MODIFIED MAXIMUM DRY DENSITY AS MEASURED BY ASTM D1557 FOR SANDS AND LABORATORY TEST ASTM D2922 FOR COHESIVE SOIL.
2.5 SOIL UNDER FLAT BOTTOMED TANKS SHALL BE COMPACTED AS PER NOTE 2.4 TO ACHIEVE 98% MODIFIED MAXIMUM DRY DENSITY.
2.6 ALL EXCAVATIONS FOR FOOTINGS SHALL HAVE A MINIMUM THICKNESS OF 75mm OF LEAN MIX CONCRETE (GRADE IN ACCORDANCE WITH STANDARD SPECIFICATION) APPLIED IMMEDIATELY ON COMPLETION OF THE EXCAVATION. NO EXCAVATION SHALL BE LEFT OPEN OVERNIGHT WITHOUT POURING LEAN MIX CONCRETE.
2.7 TO FACILITATE DRAINAGE AWAY FROM CONCRETE STRUCTURES. THE CONCRETE CONTRACTOR SHALL BACKFILL AND COMPACT LOCALLY BEHIND ALL KERBS, AND AROUND THE EDGES OF ALL SLABS AND ISOLATED PEDESTALS, TO THE DETAILS SHOWN ON THE DESIGN DRAWINGS AND AS DIRECTED BY THE EMPLOYER.

3.0 FORMWORK :

3.1 ALL FORM WORK AND FALSE WORK SHALL COMPLY WITH ACI 347.
3.2 ALL EXPOSED EDGES OF CONCRETE SHALL BE PROVIDED WITH A 20mm x 20mm CHAMFER OR FILLET.

4.0 CONCRETE :

4.1 ALL CONCRETE WORKS SHALL BE IN ACCORDANCE WITH STANDARD SPECIFICATION MD-101-SMEM-EG-ST-SPC-0005 AND 0006 AND ACI 301.
4.2 CONCRETE FINISHES SHALL COMPLY WITH ACI 302.1R, STANDARD SPECIFICATION MD-101-SMEM-EG-ST-SPC-0006 AND AS FOLLOWS, UNLESS NOTED OTHERWISE ON THE DESIGN DRAWING.
4.3 CONCRETE FINISHES (REFERENCE TO MD-101-SMEM-EG-ST-SPC-0005)


FINISHING UNFORMED SURFACES	
FINISH	TYPICAL APPLICATION
SCRATCHED	SURFACE OF RODS, FOUNDATIONS, BEDS, SLABS AND STRUCTURAL MEMBERS TO BE COVERED BY BACKFILL, SUBSEQUENT STAGES OF CONSTRUCTION, BONDED CONCRETE, TOPPING OR CEMENT MORTAR BED TO RECEIVE PAVING AND EXPOSED SURFACES WHERE SPECIFIED.
WOOD FLOATED	FOR WALKS, DRIVES, STEPS, RAMPS AND FOR SURFACES TO RECEIVE WATERPROOFING, INSULATION, MASTIC OR BLOCK OR TILE PAVING.
STEEL TROWEL	FOR FLOORS, PAVING, TOP OF WALLS, COPINGS OR OTHER MEMBERS EXPOSED TO WEATHERING, SURFACE BEDS AND SLABS TO RECEIVE THIN FLEXIBLE SHEET AND / OR TILE.
BROOM	SURFACE WHICH ARE FOR FOOT TRAFFIC.

FINISHING FORMED SURFACES	
FINISH	TYPICAL APPLICATION
ROUGHFORM	SURFACE AGAINST BACKFILL OR AGAINST WHICH FURTHER CONCRETE WILL BE PLACED
SMOOTHFORM	SURFACES WHICH ARE PERMANENTLY EXPOSED TO VIEW, BUT WHERE THE HIGHEST STANDARD OF FINISH IS NOT REQUIRED.
SMOOTH-RUBBED	SURFACES PROMINENTLY EXPOSED TO VIEW WHERE GOOD APPEARANCE AND ALIGNMENT ARE OF SPECIAL ARCHITECTURAL IMPORTANCE.

4.4 CONCRETE CURING SHALL COMPLY WITH ACI 308R-01.
4.5 FOR CONCRETE STRENGTH GRADES REFER STANDARD SPECIFICATION MD-101-SMEM-EG-ST-SPC-0005. DESIGNER SHALL SPECIFY CONCRETE GRADE ON DESIGN DRAWING.
4.6 ADDITIVES SHALL NOT BE USED WITHOUT PRIOR APPROVAL OF THE EMPLOYER.
4.7 THE MAXIMUM FREE FALL OF CONCRETE DURING PLACEMENT SHALL NOT EXCEED 1.5 METRES.
4.8 CONSTRUCTION JOINTS AND SLEEVES SHALL NOT BE USED IN POSITIONS OTHER THAN THOSE INDICATED ON THE DESIGN DRAWINGS WITHOUT PRIOR APPROVAL OF THE EMPLOYER.
4.9 A VAPOUR BARRIER MEMBRANE CONSISTING OF A 0.25mm POLYTHENE FILM SHALL BE PLACED UNDER ALL SLABS POURED ON GROUND.
LAP VAPOUR BARRIER MEMBRANE MINIMUM 100mm AND SEAL WITH ADHESIVE TAPE TO ENSURE A COMPLETE MOISTURE BARRIER.
4.10 STRUCTURAL CONCRETE SHALL BE IN GENERAL OF GRADE 35 MPa AND BLINDING CONCRETE OF GRADE 15 MPa (BOTH 28 DAYS COMPRESSIVE STRENGTH) UNLESS NOTED OTHERWISE.

5.0 REINFORCEMENT :

5.1 REINFORCING STEEL BAR SHALL BE DEFORMED BAR CONFORMING TO MP-101-SMEM-EG-ST-SPC-0006 AND ASTM A615/A615M, GRADE 60 UNLESS NOTED OTHERWISE.
5.2 WELDED STEEL FABRIC SHALL CONFORM TO A185/A185M AND A884/A884M.
ALL FABRIC SHALL BE SUPPLIED IN FLAT SHEETS. LAP FABRIC AS SHOWN BELOW.



5.3 SPLICES IN REINFORCEMENT SHALL BE PROVIDED IN THOSE POSITIONS SHOWN ON THE DRAWINGS. IN ALL CONCRETE ELEMENTS WITH LONG CONTINUOUS BARS, SPLICES SHALL BE STAGGERED IN ADJACENT BARS (START TO START) BY 48XBAR DIAMETER MINIMUM. SPLICES SHALL NOT BE PROVIDED WHERE CRITICAL BENDING STRESSES ARE DEVELOPED.
5.4 MINIMUM SPLICE LENGTHS FOR REINFORCEMENT SHALL BE AS FOLLOWS (AS PER ACI 318)
i) 20mm & SMALLER DIA BARS = 40x BAR DIAMETER
ii) 22mm & LARGER DIA BARS = 55x BAR DIAMETER (EXCEPT AS STATED IN SL. iii)
iii) BEAM & SLABS BOTTOM REINFORCEMENT (ALL DIA BARS) = 40x BAR DIAMETER
5.5 EXPLANATION OF NOTATION FOR REINFORCEMENT USED ON DRAWINGS :
EXAMPLE : 16-D24(002)-300B1.
16 NUMBER OF REINFORCING BARS.
D24 BAR GRADE 'D' (DEFORMED BAR) AND DIAMETER '24'.
(002) BAR MARK NUMBER (WHEN SPECIFIED).
300 DISTANCE BETWEEN BAR CENTRES.
B1 DESIGNATION OF REINFORCEMENT LAYER WHENEVER SPECIFIED (REFER DIAGRAM 1).




DIAGRAM 1- CONCRETE SLAB

T - TOP
B - BOTTOM
NF - NEAR FACE
FF - FAR FACE
EW - EACH WAY
EF - EACH FACE




DIAGRAM 2- CONCRETE BEAM




DIAGRAM 3- CONCRETE COLUMN




DIAGRAM 4- CONCRETE COLUMN

5.6 MINIMUM CONCRETE PROTECTIVE COVER FOR REINFORCEMENT SHALL BE AS FOLLOWS :

SL. NO.	DESCRIPTION	CONCRETE COVER (mm)
1	WALL	50
2	COLUMN	40
3	BEAM	40
4	FOUNDATION	50
5	SLAB	20

5.7 CONCRETE COVER SHALL NOT EXCEED 100mm TO AVOID SERIOUS SHRINKAGE CRACKS.
5.8 MINIMUM STANDARD 90° HOOK LENGTHS FOR REINFORCING BARS SHALL BE AS FOLLOWS :

BAR DIA	HOOK LENGTH	BAR DIA	HOOK LENGTH
12	200	28	350
16	200	32	400
20	250	36	440
24	300		

5.9 REINFORCEMENT SHALL BE SUPPORTED BY :
- PROPRIETARY CONCRETE SPACERS FOR FOOTINGS, GROUND SLABS AND FOUNDATIONS.
- STEEL/PLASTIC BAR CHAIRS FOR SUSPENDED SLABS, SIDE COVERS ON PEDESTAL FOOTINGS, BASES OR ANY VERTICAL SURFACES.
- BENT DEFORMED BAR SPACERS BETWEEN THE TOP AND BOTTOM REINFORCEMENT MATS.

5.10 REINFORCEMENT DETAILING SHALL BE IN GENERAL AS PER DRG. NO. MD-216-EG-CV-DED-1005 UNLESS OTHERWISE INDICATED IN RESPECTIVE DETAIL DRAWINGS.

6.0 ANCHOR BOLTS :

6.1 ANCHOR BOLT SPECIFICATION SHALL BE IN ACCORDANCE WITH MD-101-SMEM-EG-CV-SPC-0002 AND SHALL BE OF ROUND BAR MATERIAL MINIMUM GRADE 36 STEEL TO ASTM F1554.
6.2 ANCHOR BOLTS, NUTS AND WASHERS SHALL BE HOT DIPPED GALVANIZED UNLESS FABRICATED FROM STAINLESS STEEL.
6.3 PROPRIETARY ANCHORS SHALL BE M20 CHEMICAL ANCHORS INSTALLED STRICTLY IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS AND COMPLY WITH ANCHOR BOLT SPECIFICATION MD-101-SMEM-EG-CV-SPC-0002.
6.4 ALL ANCHOR BOLTS SHALL HAVE ONE WASHER AND ONE NUT UNLESS NOTED OTHERWISE ON THE DESIGN DRAWING.
6.5 RESIN GROUTING OF ANCHOR BOLTS AND/OR DOWEL BARS INTO PREFORMED OR DRILLED HOLES SHALL BE CARRIED OUT USING AN EMPLOYER APPROVED INJECTION SYSTEM INSTALLED STRICTLY IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS.
6.6 ALL FABRICATED ANCHOR BOLTS SHALL BE TIGHTENED TO THE SNUG TIGHT CONDITION. ALL PROPRIETARY ANCHOR BOLTS SHALL BE TIGHTENED TO THE MANUFACTURER'S RECOMMENDED TORQUE.

7.0 PENETRATIONS AND CAST IN ITEMS :

7.1 ALL EMBEDDED ITEMS SHALL BE IN ACCORDANCE WITH STANDARD SPECIFICATION MD-101-SMEM-EG-ST-DST-0006.
7.2 ALL EMBEDDED STEEL WORK OTHER THAN REINFORCEMENT SHALL BE GRADE 250 OR 300 AND SHALL BE PROTECTED AGAINST CORROSION USING PROTECTIVE PAINT ON EXPOSED SURFACE AS MENTIONED IN APPROVED DESIGN CRITERIA (VIDE DOCUMENT MD-216-1000-EG- ST-CRT-1001)
7.3 ALL CAST-IN PLACE STEEL WORK SHALL BE FIRMLY SECURED TO FORM WORK SUCH THAT ALL EXPOSED STEEL SURFACES REMAIN IN PLACE DURING THE CONCRETE POUR.
7.4 BEFORE POURING CONCRETE THE CONTRACTOR SHALL VERIFY REQUIREMENTS FOR ALL RELEVANT SERVICES, EMBEDDED ITEMS, BOLTS, SLEEVES ETC.
7.5 NO HOLES, CHASES OR EMBEDMENTS OTHER THAN THOSE SHOWN ON THE DRAWINGS SHALL BE MADE IN THE CONCRETE WITHOUT PRIOR APPROVAL OF THE EMPLOYER.
7.6 ALL SLABS SHALL HAVE FULLY ANCHORED RE-ENTRANT BARS AT ALL RE-ENTRANT CORNERS AS SHOWN ON THE DESIGN DRAWINGS OR STANDARD DRAWING MD-101-SMEM-EG-ST-DST-0007.

8.0 EARTHING :

8.1 FOR EARTHING REQUIREMENTS REFER DRAWING NO. MD-216-49PQ-EG-EL-STD-1035.

9.0 PROTECTIVE COATING :

9.1 NO PROTECTIVE COATING ON CONCRETE SURFACES IS REQUIRED AS PER THE SOIL REPORT OF THE PROJECT.

THE CONCRETE STANDARD NOTES SHOWN ON THIS DRAWING APPLY UNLESS NOTED OTHERWISE ON THESE STANDARD DRAWINGS OR ON THE DESIGN DRAWINGS

DOCUMENT NUMBER	REFERENCE DOCUMENTS	REV	DATE	REVISION DESCRIPTION	DRN	CHK	ENG	APP	EMP
		D01	15/03/2023	AS-BUILT	PML	SJM	SOR	AG	
		C02	08/04/2021	ISSUED FOR CONSTRUCTION AND REVISED AS MARKED (A1)	PML	SJM	SOR	AG	
		C01	21/03/2020	ISSUED FOR CONSTRUCTION	ARU	SJM	SOR	AG	
		A02	18/03/2020	REVISED AS PER EMPLOYER COMMENTS ON 03/03/2020	ARU	SJM	SOR	AG	
				AND AS MKD. (A2)					
MD-101-SMEM-EG-ST-DST-0001	CONCRETE GENERAL NOTES	A01	05/02/2020	ISSUED FOR INFORMATION	ARU	SJM	SOR	AG	

RESERVED FOR VENDOR LOGO AND DRAWING NUMBER

LARSEN & TOUBRO

This drawing is the property of LARSEN & TOUBRO and must not be passed on to any person or body not authorized by us to receive it nor be copied or otherwise made use either in full or in part by such person or body without our prior permission in writing.

Outotec

The content of these documents are the sole property of Outotec Oyj. Any rights not expressly granted herein are reserved. Reproduction, transfer or distribution of part or all of the contents in any form without prior written permission of Outotec is prohibited.

MA'ADEN معادن
Saudi Arabian Mining Company شركة التعدين العربية السعودية

This document and the information contained herein is Ma'aden proprietary know-how. This document or any part thereof should not be reproduced, stored in a retrieval system or transmitted by any means, electronic or otherwise, or divulged without prior written permission of Ma'aden.

LARSEN & TOUBRO DRAWING NUMBER: 019045_900_C_D_24350_001 | REVISION: 4
OUTOTEC DRAWING NUMBER: 900707__GAU01__ZZ01__CTB17__10001 | DOCUMENT ID: OU100666796 | REVISION: 4

DRAWN	ARU	03/02/2020
CHECKED	SJM	04/02/2020
ENGINEER	SOR	29/01/2020
APPROVED	AG	05/02/2020
EMPLOYER		
SCALE 1:100	A1	

MANSOURAH - MASSARAH GOLD PROJECT
ALL AREAS
CIVIL STANDARDS
GENERAL NOTES FOR CIVIL WORKS

DRAWING NUMBER: MD-216-1000-EG-CV-DED-1001 | REV: D01